

Work During Calendar Year 2022

CDOT ANNUAL PAVEMENT PROJECT PROJECTIONS

Date

11/4/21

Region	Asphalt*	Asphalt Binder	Concrete*	Concrete*	Surface Treatments	Emulsion
	Ton	Ton	SY	CY	SY	Gal
1	177,314	9,863	76,000	22,167	34,895	-
2	301,025	16,556	798,000	185,500	395,000	-
3	396,100	23,877	4,838	1,344	329,000	150,750
4	153,838	8,461	-	-	-	-
5	267,181	18,493	26,780	50,396	555,019	244,208
Totals*	1,295,458	77,250	905,618	259,406	1,313,914	394,958

Region	58-28*	58-34*	64-22 *	64-28*	76-28*	CRS-2P*
	tons	tons	tons	tons	tons	Gal
1	-	-	-	-	9,863	-
2	11,496	-	-	2,310	2,750	-
3	7,197	2,570	647	6,725	6,738	150,750
4	-	1,312	1,659	5,490	-	-
5	7,614	4,482	-	5,164	1,234	244,208
Totals*	26,307	8,364	2,306	19,689	20,585	394,958

Region	S	SX	SG	SMA	ST	Other	Single Chip Seal SY	Double Chip Seal SY
	tons	tons	tons	tons	tons	tons		
1	-	29,041	-	148,273	-	-	-	-
2	-	256,400	-	-	44,625	-	-	-
3	-	359,500	-	-	36,600	-	285,000	44,000
4	-	153,838	-	-	-	-	-	-
5	-	152,546	-	93,894	89,802	-	555,019	-
Totals*	-	951,325	-	242,167	171,027	-	840,019	44,000

Notes:

Disclaimer: The projects listed and the quantities associated with each project are approximate and based on the best information available at the time. These are primarily large paving projects. There may be changes to the projects and quantities listed at any time, based on shifting priorities, funding, potential pavement type selection committee results, alternative bids, etc., without notice.

CDOT Historical Projected and Actual Data

Year	Projected Tons	Actual Tons	Percentage
2012	1,198,088	1,153,751	96%
2013	1,264,929	1,248,582	99%
2014	1,290,679	1,370,184	106%
2015	1,154,054	1,343,902	116%
2016	1,318,433	1,673,068	127%
2017	1,009,944	1,036,222	103%
2018	997,927	1,437,500	144%
2019	1,259,920	1,130,102	90%
2020	978,270	1,342,174	137%
2021	938,056	**	
2022 *	1,295,458		

Notes:

** Actual tons for 2021 are still being compiled.

* The Projected tons are based on Region Estimates for Construction Season 2022, and may include tonnage from other FY budgets besides FY 2022.

**Work During Calendar Year 2022
CDOT ANNUAL ASPHALT PAVEMENT
PROJECT PROJECTIONS**

Date 11/4/21

Region	Project No.	Location	BMP	EMP	Sub Account	Gradation	Gyrations	Tons of Mix	Binder Type	Binder Tons	Unique Specs*	Ad Period**	Start Date	HIPIR, CIPR
1	NHPP 0703-472	I-70 from Wadsworth to Pecos St.	269.4	273.3	23567	SMA	100	40,613	76-28	2,234	SMA	Early	Spring	
1	NHPP 0852-110	US-85 from Florida Ave to I-25	209.2	210.9	19934	SMA	100	8,568	76-28	471	SMA	Early	Spring?	
1	NHPP 2873-189	US-287C Federal Blvd. Colfax to I-70	282.7	285.7	21801	SMA	100	12,902	76-28	710	SMA	Early	Spring	
1	NHPP 0021-041	SH-002A Colorado Blvd. MLK to 52nd Ave.	7.45	9.65	23554	SMA	100	22,000	76-28	1,320	SMA	Early	Spring	
1	NHPP 0703-465	I-70 from Floyd Hill to Chief Hosa	246.5	252.9	23178	SMA	100	64,190	76-28	3,530	SMA	Early	Spring	
1	NHPP 072A-047	SH 72 (Ward Rd from I-70 to Indiana St)	0	3.6	23176	SX	100	29,041	76-28	1,597	Voids Acceptance	Early	Summer	

Region 1 Summary	
76-28	9,863
70-28	0
64-28	0
58-34	0
64-22	0
58-28	0
Unknown	0
R1 PG Tons	9,863
R1 Mix Tons	177,314

Region 1 Summary	
S	0
SX	29,041
SG	0
SMA	148,273
ST	0
Other	0

2	NH 0504-911	US 50B Pueblo County Surface Treatment	315.0	330.0	23546	SX	75	50,000	76-28	2,750		Early	Spring	
2	STA 207A-004	SH 209A and SH 266A Otero County Surface Treatment	0/0	5.9/11.5	21191	SX	75	25,000	58-28	1,375		Late	Spring	
2	STR 1604-014	US 160C and SH 100A Baca County Surface Treatment	463.5	474.5	21982	ST	50	9,625	58-28	529		Late	Summer	
	STR 1604-014	US 1060C and SH 100A Baca County Surface Treatment	463.5	474.5	21982	SX	75	14,400	58-28	792		Late	Summer	
2	STR 160A-034	US 160A La Veta Pass Surface Treatment	278.6	294.4	21837	SX	75	47,000	58-28	2,585		Early	Spring	
2	NH 0242-092	US 24A Teller County Surface Treatment	284.5	291.4	23188	SX	75	42,000	64-28	2,310		Early	Summer	
2	STR 0961-017	SH 96A Custer County Surface Treatment	0.0	26.0	23239	ST	50	25,000	58-28	1,375		Early	Spring	
	STR 0961-017	SH 96A Custer County Surface Treatment	0.0	26.0	23239	SX	75	46,000	58-28	2,530		Early	Summer	
2	STA 067A-048	SH 67A Custer/Fremont Counties Surface Treatment	0.0	11.0	24263	ST	50	10,000	58-28	550		Late	Summer	
	STA 067A-048	SH 67 Custer/Fremont Counties Surface Treatment	0.0	11.0	24263	SX	75	15,000	58-28	825		Late	Summer	
2	STA M240-001	US 285/SH 9 Intersection Improvements	64.6	64.9	20638	SX	75	17,000	58-28	935		Early	Summer	

Region 2 Summary	
76-28	2,750
70-28	0
64-28	2,310
58-34	0
64-22	0
58-28	11,496
Unknown	0
R2 PG Tons	16,556
R2 Mix Tons	301,025

Region 2 Summary	
S	0
SX	256,400
SG	0
SMA	0
ST	44,625
Other	0

3	NHPP 0703-463	I-70 Silverthorne to EJMT Phase I	206	210.7	23075	SX	75	27,200	58-28	1,541	Night Paving	Early		
3	NHPP 0401-025	US 40 Sand Springs Gulch - Craig	80.7	92.0	23126	SX	75	26,550	58-34	1,593	Voids Acceptance	Early		
3	NHPP 0401-025	US 40 Sand Springs Gulch - Craig	80.7	92	23126	SX	75	18,250	64-28	1,095	Voids Acceptance	Early		
3	NHPP 0063-063	US 6 North Avenue	30.7	34.4	23110	SX	100	16,400	76-28	982	Voids Acceptance	Early		
3	NHPP 5502-108	US 50/550 Montrose Resurfacing	86	91.7	23103	SX	100	30,500	76-28	1,880	Voids Acceptance	Early		
3	NHPP 5502-108	US 50/550 Montrose Resurfacing	86.0	91.7	23103	SX	100	27,800	64-28	1,714	Voids Acceptance	Early		

**Work During Calendar Year 2022
CDOT ANNUAL ASPHALT PAVEMENT
PROJECT PROJECTIONS**

Date 11/4/21

Region	Project No.	Location	BMP	EMP	Sub Account	Gradation	Gyrations	Tons of Mix	Binder Type	Binder Tons	Unique Specs*	Ad Period**	Start Date	HIPIR, CIPR
3	NHPP 0063-062	US 6 & SH 141 Mesa County Resurfacing	38.16	46.1	23109	SX	75	19,500	76-28	1,173	Voids Acceptance	Early		
3	NHPP 0063-062	US 6 & SH 141 Mesa County Resurfacing	156.74	159.9	23109	ST	75	4,600	64-22	276	Voids Acceptance	Early		
3	STR 092-032	SH 92 West of Austin Resurfacing	4.2	7	24139	SX	75	7,400	64-28	403		Early		
3	STR 092-032	SH 92 West of Austin Resurfacing	4.2	7	24139	ST	75	3,400	58-28	288		Early		
3	NHPP 0702-383	EB Aux Frisco to Silverthorne	202.6	206.2	22381	SX	75	16,150	58-34	977		Early		
3	NHPP 0702-383	EB Aux Frisco to Silverthorne	202.6	206.2	22381	SX	75	23,150	58-28	1,402		Early		
3	STR 139A-035	SH 139 Douglas Pass N & S Rural Resurface	37.5	52.7	23500	SX	75	26,600	64-28	1,599		Early		
3	STR 139A-035	SH 139 Douglas Pass N & S Rural Resurface	37.5	52.7	23500	ST	75	18,900	58-28	1,246		Early		
3	NHPP 0701-247	I-70 Parachute to Rulison	75.5	81.7	23060	SX	100	34,450	76-28	1,978	Voids Acceptance	Early		
3	NHPP 0701-247	I-70 Parachute to Rulison	75.5	81.7	23060	SX	100	6,450	64-22	371	Voids Acceptance	Early		
3	STR 092A-031	SH 92 Hotchkiss to Crawford	20.0	31.7	23577	SX	75	23,000	64-28	1,131		Early		
3	STR 092A-031	SH 92 Hotchkiss to Crawford	20	31.7	23577	ST	75	9,700	58-28	951		Early		
3	NHPP 0131-057	SH 13 GarCo Rio Blanco Hill	11.3	16.2	17881	SX	100	13,500	64-28	783	Voids Acceptance	Early		
3	NHPP 0131-057	SH 13 GarCo Rio Blanco Hill	11.3	16.2	17881	SX	100	30,500	58-28	1,769	Voids Acceptance	Early		
3	NHPP 0821-111	SH 82 AABC to Aspen	37.8	40.2	23134	SX	100	12,100	76-28	725		Early		

Region 3 Summary	
76-28	6,738
70-28	0
64-28	6,725
58-34	2,570
64-22	647
58-28	7,197
Unknown	0
R3 PG Tons	23,877
R3 Mix Tons	396,100

Region 3 Summary	
S	0
SX	359,500
SG	0
SMA	0
ST	36,600
Other	0

4	STA 0142-071	SH14C: Pawnee Pass to Sterling Part 2	227.2	234.1	24206	SX	75	30,167	64-22	1,659	Full Depth Reclamation	Early		
4	STA 0142-071	SH14C: Pawnee Pass to Sterling Part 2	227.2	234.1	24206	SX	75	28,373	64-28	1,561	Full Depth Reclamation	Early		
4	STA 0712-019	SH 71: Climbing Lanes	102.0	174.4	23160	SX	100	6,720	64-28	370	Voids Acceptance	Early		
4	STA 001A-005	SH1 Wellington South Resurfacing	0.0	10.0	24418	SX	75	36,017	64-28	1,981	Voids Acceptance	Early		
4	STA 3852-015	US 385 Holyoke North	278.0	290.0	20867	SX	75	28,706	64-28	1,579	Voids Acceptance	Early		
4	ER 007A-035	PR SH7 Flood Repairs CP2	19.0	33.0	24414	SX	75	23,855	58-34	1,312	Voids Acceptance	Early		

Region 4 Summary	
76-28	0
70-28	0
64-28	5,490
58-34	1,312
64-22	1,659
58-28	0
Unknown	0
R4 PG Tons	8,461
R4 Mix Tons	153,838

Region 4 Summary	
S	0
SX	153,838
SG	0
SMA	0
ST	0
Other	0

5, 3	C 149A-028	SH 149 Creed North, Lake City North	23.0	93.0	23490	SX	75	63,965	58-34	3,518	Voids Acceptance	Early	3/14/2022	CIPR
------	------------	-------------------------------------	------	------	-------	----	----	--------	-------	-------	------------------	-------	-----------	------

**Work During Calendar Year 2022
CDOT ANNUAL ASPHALT PAVEMENT
PROJECT PROJECTIONS**

Date 11/4/21

Region	Project No.	Location	BMP	EMP	Sub Account	Gradation	Gyrations	Tons of Mix	Binder Type	Binder Tons	Unique Specs*	Ad Period**	Start Date	HIPR, CIPR
5, 3	C 149A-028	SH 149 Creed North, Lake City North	23.0	93.0	23490	ST	75	18,622	58-28	1,024	Voids Acceptance	Early	3/14/2022	CIPR
5	NHPP 1602-182	US 160 Pagosa Springs	135.6	144.2	23505	SMA	100	20,000	64-28	1,100	Night Paving	Early	4/22/2022	
5	NHPP 1602-182	US 160 Pagosa Springs	135.6	144.2	23505	ST	75	14,000	58-28	770	Voids Acceptance	Early	4/22/2022	
5	NHPP 1602-187	US 160 Monte Vista East	215.9	226.3	22966	SMA	100	32,830	64-28	1,806	SMA	Early	3/1/2022	
5	NHPP 1602-187	US 160 Monte Vista East	215.9	226.3	22966	ST	75	13,712	58-28	754	Voids Acceptance	Early	3/1/2022	
5	NHPP 1602-187	SH 370	4.0	8.0	22966	SX	75	5,520	58-34	304	Voids Acceptance	Early	3/1/2022	
5	NHPP 1602-187	SH 370	4.0	8.0	22966	ST	75	4,368	58-28	240	Voids Acceptance	Early	3/1/2022	
5	NHPP 1601-083	US 160 Four Corners to Aztec Creek	0.0	8.0	22193	SX	100	22435*	76-28	1,234	Full Depth Reclamation	Early	3/1/2022	
5	NHPP 1601-083	US 160 Four Corners to Aztec Creek	0.0	8.0	22193	SX	75	46626*	58-28	2,564	Full Depth Reclamation	Early	3/1/2022	
5	C 0502-089	US 50 Poncha West	210.0	217.0	23497	SX	75	12,000	58-34	660	Voids Acceptance	Late	7/22/2021	
5	C 0502-089	US 50 Poncha West	210.0	217.0	23497	ST	75	8,000	58-28	440	Voids Acceptance	Late	7/22/2021	
5	NHPP 5502-081	US 550 Ouray to Colona	93.8	115.6	20121	SMA	100	41,064	64-28	2,259	SMA	Early	4/1/2021	
5	NHPP 5502-081	US 550 Ouray to Colona	93.8	115.6	20121	ST	75	31,100	58-28	1,711	Voids Acceptance	Early	4/1/2021	
5	NHPP 5502-081	US 550 Ouray to Colona	93.8	115.6	20121	SX	75	2,000	58-28	110	Voids Acceptance	Early	4/1/2021	

Region 5 Summary	
76-28	1,234
70-28	0
64-28	5,164
58-34	4,482
64-22	0
58-28	7,614
Unknown	0
R5 PG Tons	18,493
R5 Mix Tons	267,181

Region 5 Summary	
S	0
SX	152,546
SG	0
SMA	93,894
ST	89,802
Other	0

* Pavement Type TBD

State Totals	
76-28	20,585
70-28	0
64-28	19,689
58-34	8,364
64-22	2,306
58-28	26,307
Unknown	0
Total PG Tons	77,250
Total Mix Tons	1,295,458

Disclaimer: The projects listed and the quantities associated with each project are approximate and based on the best information available at the time. These are primarily large paving projects. There may be changes to the projects and quantities listed at any time, based on shifting priorities, funding, potential pavement type selection committee results, alternative bids, etc., without notice.

* Examples of Unique Specifications include: SMA, RAP, FDR (full-depth reclamation), night paving, Void Acceptance (Voids), CIPR (Cold In Place Recycle, HIPR (Hot in Place Recycle)

** Anticipated Advertisement Date:
Early - construction likely during the year - ad date prior to July 1
Late - construction possible during the year - ad date after July 1

Work During Calendar Year 2022
CDOT ANNUAL CONCRETE PAVEMENT
PROJECT PROJECTIONS

Date 11/4/2021

Region	Project No.	Location	BMP		EMP	Sub Account	Square Yards	Thickness (Inches)	Cubic Yards	Fast Track (%)	Unique Specs	Ad Period*	Start Date
1	NHPP 0761-238	I 76 York to Dahlia	7.024	8.685	23599	76,000	10.5	22,167	0			Early	
1	STA 0252-459	I-25 from State Highway 86 to Castle Pines Parkway	183.9	188.1	21791			0					
R1 Totals						76,000		22,167					
2	STM 1151-038	SH 115A El Paso County Corridor Project	18	39	22903	700,000	8	155,556	1			Late	Late
2	STA 2872-019	US 287B Lamar to Kit Carson Passing Lanes - INFRA	85	133	22210	98,000	11	29,944	0			Late	Spring
R2 Totals						798,000		185,500					
3	NHPP 0821-111	SH 82 AABC to Aspen	37.8	40.2	23134	4,838	10	1,344				Early	
R3 Totals						4,838		1,344					
4													
R4 Totals						0		0					
5	NHPP 5502-081	US 550 Ouray to Colona	90.8	91	20121	1,500	8	333		Fast Track		Early	1-Apr
5	NHPP 1601-083	US 160 Four Corners to Aztec Creek	0.0	8.0	22193	225280 *	8	50,062				Early	3/1/2022
* Pavement Type TBD						R5 Totals	26,780		50,396				

	Square Yards		Cubic Yards
State Total	905,618		259,406

Early - construction likely during the year - ad data
Late - construction possible during the year - ad data

Disclaimer: The projects listed and the quantities associated with each project are approximate and based on the best information available at the time. These are primarily large paving projects. There may be changes to the projects and quantities listed at any time, based on shifting priorities, funding, potential pavement type selection committee results, alternative bids, etc., without notice.

**Work During Calendar Year 2022
CDOT ANNUAL SURFACE TREATMENT
PROJECT PROJECTIONS**

Date 11/4/21

Region	Project No.	Location	BMP	EMP	Sub Account	Treatment Type	Square Yards	Emulsion Type	Emulsion Gallons	Ad Period**	Start Date
1	STA. 0881-028	SH-88 from Alameda Ave. to Louisiana Ave.	2.1	3.2	21231	Ultrathin Bonded Wearing Course	34,895	styrene-butadiene block co-polymer (S.B.)		Early	
1											

Region 1 Summary	
CRS-2P	0
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0
ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	0

Region 1 Summary	
Single Chip Seal	0
Chip Seal with RAP	0
Double Chip Seal	0
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0
Fog Coat w/ Sand Seal	0
Microsurfacing	0

Total Surface Treatments SY	34,895
-----------------------------	--------

2	NH 0504-911	US 50B Pueblo County Surface Treatment	322	324.5	23546	Microsurfacing	60,000	Unknown	Unknown	Early	Spring
2	STR 0505-050	US 50B La Junta Preventative Maintenance	377	382	21825	Microsurfacing	335,000	Unknown	Unknown	Early	Spring

Region 2 Summary	
CRS-2P	0
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0
ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	0

Region 2 Summary	
Single Chip Seal	0
Chip Seal with RAP	0
Double Chip Seal	0
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0
Fog Coat w/ Sand Seal	0
Microsurfacing	395,000

Total Surface Treatments SY	395,000
-----------------------------	---------

3	23612	SH 133 Bowie	11.4	23.8	23612	Single Chip Seal	285,000	CRS-2P	111,150	Early	
3	NHPP 0063-062	US 6 & SH 141 Mesa County Resurfacing	43.3	46.1	23109	Double Chip Seal	44,000	CRS-2P	39,600	Early	

*Fog will be CSS-1H

*Fog will be CSS-1H

Region 3 Summary	
CRS-2P	150,750
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0

Region 3 Summary	
Single Chip Seal	285,000
Chip Seal with RAP	0
Double Chip Seal	44,000
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0

ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	150,750

Fog Coat w/ Sand Seal	0
Microsurfacing	0

Total Surface Treatments SY	329,000
-----------------------------	---------

4											
4											

Region 4 Summary	
CRS-2P	
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0
ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	0

Region 4 Summary	
Single Chip Seal	0
Chip Seal with RAP	0
Double Chip Seal	0
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0
Fog Coat w/ Sand Seal	0
Microsurfacing	0

Total Surface Treatments SY	0
-----------------------------	---

5	NHPP 2852-020	US 285 Monte Vista North	51.4	77.5	20628	Single Chip Seal	555,019	CRS-2P	244,208	Early	Jun-22
5	NHPP 2852-020	US 285 Monte Vista North	77.5	86.3	20628	Microsurfacing		CQS-1hP		Early	Jun-22

Region 5 Summary	
CRS-2P	244,208
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0
ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	244,208

Region 5 Summary	
Single Chip Seal	555,019
Chip Seal with RAP	0
Double Chip Seal	0
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0
Fog Coat w/ Sand Seal	0
Microsurfacing	0

Total Surface Treatments SY	555,019
-----------------------------	---------

--	--	--	--	--	--	--	--	--	--	--	--

State Totals	
CRS-2P	394,958
CRS-2R	0
CMS-2P	0
HFRS-2P	0
HFMS-2P	0
CSS-1	0
HFMS2sP	0

State Summary	
Single Chip Seal	840,019
Chip Seal with RAP	0
Double Chip Seal	44,000
Double Chip Seal w/ Fabric	0
Cape Seal	0
Hot Chip Seal	0
Slurry Seal	0

ERA	0
ARA	0
ARA-1P	0
Unknown	0
Total Emulsion Gal.	394,958
Total Surface Treatments SY	1,313,914

Fog Coat w/ Sand Seal	0
Microsurfacing	395,000

Disclaimer: The projects listed and the quantities associated with each project are approximate and based on the best information available at the time. These are primarily large paving projects. There may be changes to the projects and quantities listed at any time, based on shifting priorities, funding, potential pavement type selection committee results, alternative bids, etc., without notice.

** | Advertisement Date:
 Early - construction likely during the year - ad date prior to July 1
 Late - construction possible during the year - ad date after July 1